ALS Canada Ltd.

2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alsglobal.com

To: **LAKE SHORE GOLD - EXPLORATION**
1515 GOVERNMENT ROAD S.
P.O. BOX 1067
TIMMINS ON P4R 1N4

Finalized Date: 24-OCT-2010
Account: LSGEXPV

CERTIFICATE TM10152377

Project: 30700

P.O. No.:

This report is for 2 Drill Core samples submitted to our lab in Timmins, ON, Canada on 18-OCT-2010.

The following have access to data associated with this certificate:

ANTHONY CAMUTI ACCOUNTS PAYABLE LSG DATA BASE WEBTRIEVE	STEPHEN CONQUER RENO PRESSACCO	JUAN FIGUEROA TOM SAVAGE

SAMPLE PREPARATION

ALS CODE	DESCRIPTION
WEI-21	Received Sample Weight
LOG-21	Sample logging - ClientBarCode
CRU-21	Crush entire sample >70% -6 mm
PUL-21	Pulverize entire sample
WSH-22	"Wash" pulverizers
SCR-21	Screen to -100 um

ANALYTICAL PROCEDURES

ALS CODE	DESCRIPTION	INSTRUMENT
Au-SCR21	Au Screen Fire Assay - 100 um	WST-SIM
Au-AA25	Ore Grade Au 30g FA AA finish	AAS
Au-AA25D	Ore Grade Au 30g FA AA Dup	AAS

To: **LAKE SHORE GOLD - EXPLORATION**
ATTN: JUAN FIGUEROA
1515 GOVERNMENT ROAD S.
P.O. BOX 1067
TIMMINS ON P4R 1N4

This is the Final Report and supersedes any preliminary report with this certificate number. Results apply to samples as submitted. All pages of this report have been checked and approved for release.

Signature:
Colin Ramshaw, Vancouver Laboratory Manager

ALS Canada Ltd.

2103 Dollarton Hwy
North Vancouver BC V7H 0A7
Phone: 604 984 0221 Fax: 604 984 0218 www.alsglobal.com

To: **LAKE SHORE GOLD - EXPLORATION**
1515 GOVERNMENT ROAD S.
P.O. BOX 1067
TIMMINS ON P4R 1N4

Finalized Date: 24-OCT-2010
Account: LSGEXPV

Project: 30700

CERTIFICATE OF ANALYSIS TM10152377

Sample Description	Method Analyte Units LOR	WEI-21 Recvd Wt. kg 0.02	Au-SCR21 Au Total ppm 0.05	Au-SCR21 Au (+) F ppm 0.05	Au-SCR21 Au (-) F ppm 0.05	Au-SCR21 Au (+) m mg 0.001	Au-SCR21 WT. + Fr g 0.01	Au-SCR21 WT. - Fr g 0.1	Au-AA25 Au ppm 0.01	Au-AA25D Au ppm 0.01
G0614668		1.48	9.26	113.5	2.95	9.553	84.09	1390.0	2.82	3.08
G0614672		5.33	3.06	87.6	2.14	4.978	56.81	5245	2.36	1.92