We are committed to providing <u>accessible customer service</u>. If you need accessible formats or communications supports, please <u>contact us</u>.

Nous tenons à améliorer <u>l'accessibilité des services à la clientèle</u>. Si vous avez besoin de formats accessibles ou d'aide à la communication, veuillez <u>nous contacter</u>.



REPORT ON 2017 EXPLORATION

FOR

GOLD CACHE INC.

(CLIENT #407356)

GOLD CACHE PROPERTY

DAWSON ROAD LOTS AND HORNE TOWNSHIP

NTS 53A/12 **UTM COORDINATES MAP DATUM NAD 83** 0287901E / 5385013N

THUNDER BAY MINING DIVISION

Prepared by Terry Yahn Dec 2017

INTRODUCTION

We have focused our work for 4 days within claim 1173909 (6 claim block) to explore high potential areas for exploration work. Past assay results in this zone have encouraged us to continue to sample the area.

Within the boundaries of this claim are Pillow Lava extrusions which extend to the west and southwest. This entire area consists of bands of mineralization with most gold findings in the quartz veins of Mafic rock.

The Gold Cache Project contains 5 properties with 53 Claim units. It is situated 80 kms west of the city of Thunder Bay on Hwy 11/17, at Shabaqua. Highway access is available to this property.

PROJECT HISTORY

This block of claims, staked starting in 1994, once contained 93 mining units in 28 contiguous mining claims straddling the Dawson Road Lots and Horne Township, with one claim in Laurie Township. One of the main features of the property is the caldera-like structure covering approximately one third of the claim block.

During the past twenty-three years, the Shabaqua area has become one of the most active areas for mineral exploration in Northwestern Ontario. Much of the recent staking activity radiated from this structure. The subject property (in part) triggered the regional staking frenzy in 1995. It was surrounded by quality exploration companies, three of which obtained land positions on both sides of the subject property. Over twenty-five publicly traded companies swarmed into this "emerging gold camp", which is now referred to by the industry as the "Matawin Gold Belt".

During 1996 and 1997 considerable line cutting and geophysical surveys were conducted by most of the companies in the area. In 1997 several of the companies conducted diamond drill programs, with at least 12 holes drilled resulting and results up to .300 oz/t. Au. Expectations for the area remain high.

More robust exploration continued in the late 90's and right up to 2016. Although it had slowed down somewhat from its previous pace, the work simply became more concentrated (targeted) and results continued to improve. Assays in the range of .400 oz/t to 1.400 oz/t were now being found in the key properties.

In 2001 thru to 2017 work performed on nearby claims continued to yield good results with additional assays in the 1.250 oz/t range. There has been another bump in activity during 2004/06 with additional mining companies taking over some claims and actively testing the area. Almost 70 % of the area has now been re-staked and encircles our existing claims.

01:03:00 p.m.

From Sept 21 to Sept 24th we were on site for 4 days with a John Deere 310G Backhoe. This size machine is great for removing more of the topsoil because of the small bucket size, where as a larger machine leaves lots of loose dirt. The smaller backhoe however puts in longer days to complete its work.

During these days we worked within claim 1173909 which is covered in this report.

Our purpose on these days was to explore new sites which had been recently exposed (clear cut) by forestry work adjacent to our previous trenches.

Samples on this claim had brought in previous gold assays of up to 54.505 g/t. Those deposits had been found by tracking low level assays to better ground and that is what we will continue to do.

DAILY LOG FOR THIS PROJECT

Target rocks – The primary rock type in this area of the claim is Mafic with fine grains like a Basalt, but moves towards a Rhyolite with courser grains in some sections. In both cases we are looking for a target rock which is like other gold bearing assays where there was an abundance of quartz infused in the rock or by way of small spider veins throughout. We are looking for larger forming Pyrite cubes within those samples. In some cases, larger "smoky" quartz veins were visible.

THURSDAY SEPT 21, 2017

volunteer thunderbay

TERRY YAHN - (One truck/vehicle, rock hammers, safety vests and supplies, GPS, compass, pen flare with bear bangers)

SMALL JOHN DEERE 310G BACKHOE - SCOTT TIMMINS

We began our work in an area directly south of our main trenches. This trench was later labeled as 660/17 at the time we sampled the area. We spent a full day in this area and methodically cleared and cleaned a long trench which we felt could provide us with good assay results, as did similar areas directly north.

We examined the rock as we progressed and then would allow the operator to continue. There was no water source nearby to help clean the rock but there was a forecast for rain.

It was a long process with the John Deere but the smaller bucket also gave us a better look at the uncovered rock because it was able to clean it off better. It was able to brake off rock from any ridges that it uncovered.

I viewed and examined exposed rock when it was safe to do so.

FRIDAY SEPT 22, 2017

TERRY YAHN - (One truck/vehicle, rock hammers, safety vests and supplies, GPS, compass, pen flare with bear bangers)

SMALL JOHN DEERE 310G BACKHOE - SCOTT TIMMINS

On this day we moved to the southern portion of the claim to take advantage of the

P011

volunteer thunderbay 01:03:29 p.m. 01-08-2018

clearcutting that had taken place. We cleared two trenches in this area. Later they were recorded as Trench 671/17 and 655/17. They were only 50 meters apart and could almost be considered an extension but there was enough of a difference that we treated them as separate trenches.

Later that day we moved back towards the north and worked at clearing an outcrop. This area was later determined to not yield any significant mineralization and we didn't take a sample at the time. There wasn't a lot of overburden, but it took up much of our time that afternoon.

We would later label the area as a test pit 661/17.

SATURDAY SEPT 23, 2017

TERRY YAHN - (One truck/vehicle, rock hammers, safety vests and supplies, GPS, compass, pen flare with bear bangers)

SMALL JOHN DEERE 310G BACKHOE – SCOTT TIMMINS

We started the day back at our test pit 661/17 to continue to test the area. We cleared off almost 20 meters of overburden (with no change in mineral consistency).

We moved to the west about 50 meters to look for change in the mineralization but without results. This new area was again labeled as a test pit and assigned Test Pit 656/17. This pit was filled back in.

The clear cuts provided us with targets for exploration but created a situation where we tried to test areas as we travelled. We eliminate several areas as we headed to the north, to begin again in the morning.

The intent was not to forget about these areas, but not to pursue them at this time.

SUNDAY SEPT 24, 2017

TERRY YAHN - (One truck/vehicle, rock hammers, safety vests and supplies, GPS, compass, pen flare with bear bangers)

SMALL JOHN DEERE 310G BACKHOE - SCOTT TIMMINS

We started this day with another test pit, 100 meters to the north of those worked on the

P012

6226435

volunteer thunderbay

previous day. This test pit was labeled 657/17 and was filled back in. However, as we continued to move north, we did end up creating Trench 658/17.

This area was 320 meters directly east of trench 660/17 where we had started on Sept 21th, and which we expected to receive helpful assay results.

We decided to end the day by taking a sample close to the Hydro Line and the eastern extent of our main trenches. The target area was close to the road but near a water supply that could interfere with our trench. Trench 659/17 was dug down to bedrock. The water did not seem to be a problem and we were able to take a sample.

However, when we returned the next day to work on other claims, I noted that the trench was full of water which had seeped in over time.

WEDNESDAY SEPT 27, 2017

On this day the Backhoe was moved to claim #1173912 and its time and related costs were included in the Assessment report prepared for that claim and reported on Oct 3, 2017. See Transaction Number #W1740-01890 approved November 21, 2017 on claim #1173912.

01-08-2018

GPS CO-ORDINATES (NAD 83 DATUM USED) UTM ZONE 16U

PIT#	TAG #'S	EASTING	NORTHING	TO #1 POST
655/17	473553	0287983	5385035	1.1 km @ 19 Degrees
658/17	473554	0288100	5385409	756 meters @ 21°
659/17	473555	0288192	5385522	608 meters @ 15°
660/17	473556/57/58	0287865	5385427	843 meters @ 34°
671/17	473551/52	0287932	5385041	1.1 km @ 20 Degrees
TEST PI	T 656/17 FILLED IN	0288096	5385224	931 meters @ 17°
TEST PI	T 657/17 FILLED IN	0288081	5385329	791 meters @ 21°
TEST PI CLEARI NOT SA	ED OVERBURDEN –	0288144	5385222	911 meters @ 12°

Pit/Trench 655/17

Located on Claim 1173909 this area located near the southern claim line.

Like several of the areas sampled, this area was made accessible because of recent forestry work.

The pit area was 4 meters by 5 meters. It drops a meter from the top to the bottom (south to north). It contained some boulders near the center.

The work had involved clearing the area with a small John Deere Backhoe. At the time of sampling water was not present in the excavated area.

The rock contains pockets of quartz with scattered Pyrite present. We took one representative sample near the center.

Assay Tag 473553 (Quartz pockets with small pyrite)

Gold (Au) 13 ppb Aluminum (Al) 4.88 % Calcium (Ca) 9.01 % Iron (Fe) 13.5 % Magnesium (Mg) 2.75 % Manganese (Mn) 3320 ppm Phosphorus (P) 308 ppm Cobalt (Co) 37.3 ppm Chromium (Cr) 86.1 ppm Copper (Cu) 109 ppm Nickel (Ni) 44.2 ppm Zinc (Zn) 135 ppm

Pit/Trench 658/17

Located on Claim 1173909 this area was chosen after a test pit was opened and refilled just south of this trench. We found an outcrop and cleared it down to expose 20 square meters of bedrock. The trench size was 4 meters wide and 5 meters long.

At the time of sampling water was not present in the immediate area of the trench.

The rock contains a high quantity of quartz infused into the rock. Pyrite was present. We took one sample below the ridge.

Assay Tag 473554 (high Quartz content with small pyrite)

Gold (Au) 1 ppb Aluminum (Al) 4.16 % Calcium (Ca) 6.55 % Iron (Fe) 7.37 % Magnesium (Mg) 3.59 % Manganese (Mn) 1280 ppm Phosphorus (P) 443 ppm Cobalt (Co) 38.7 ppm Chromium (Cr) 192 ppm Copper (Cu) 83.0 ppm Nickel (Ni) 62.7 ppm

Pit/Trench 659/17

Zinc (Zn) 38.1 ppm

Located on Claim 1173909 this area is located just south of the hydro line and west of the access road. The pit was 1 meter wide by 3 meters long and dug to a depth of 2 meters.

The pit was near a water source and we were concerned about it flooding quickly. We were able to reach bedrock without seepage. The pit eventually filled over a day or so. The rock contains quartz stringers with cubes of Pyrite present. We took one sample from the south side.

Assay Tag 473555 (Quartz stringers with pyrite cubes)

Gold (Au) 16 ppb Aluminum (Al) .85 % Calcium (Ca) 2.38 % Iron (Fe) 2.99 % Magnesium (Mg) 0.79 % Manganese (Mn) 687 ppm Phosphorus (P) 618 ppm

6226435

Cobalt (Co) 17.9 ppm Chromium (Cr) 10.9 ppm Copper (Cu) 47.2 ppm Nickel (Ni) 46.3 ppm Zinc (Zn) 15.6 ppm

<u>Pit/Trench 660/17</u>

Located on Claim 1173909 and just south of our main trenches. This area was recently opened up by clearcutting on this claim. We were attempting to match some of the gold assay values found in the main trench area.

The trench was started at the top of a ridge and we worked our way down the hill exposing bedrock as we went. The mineralization was like what we had seen 100 meters to the north. The trench contained several internal ridges and slopes. At one point there was a ridge located running across the trench about 9 meters from top and then it dropped off sharply.

A water source was not present at this site.

The rock contains quartz infused into the rock with Pyrite present. We took three samples/.

We believe that this area has the greatest potential and we will return to this trench and expand it further with cross trenches.

Assay Tag 473556 (High Quartz content with small pyrite)

Gold (Au) 4 ppb **Aluminum (Al) 5.39 %** Calcium (Ca) 1.31 % Iron (Fe) 7.59 % Magnesium (Mg) 6.01 % Manganese (Mn) 1290 ppm Phosphorus (P) 331 ppm Cobalt (Co) 53.8 ppm Chromium (Cr) 347 ppm

6226435

Copper (Cu) 76.6 ppm Nickel (Ni) 233 ppm

Assay Tag 473557 (High Quartz content with pyrite along sides)

Zinc (Zn) 100 ppm

Gold (Au) 3 ppb

Aluminum (Al) 4.92 %

Calcium (Ca) 2.77 %

Iron (Fe) 7.15 %

Magnesium (Mg) 5.31 %

Manganese (Mn) 1280 ppm

Phosphorus (P) 314 ppm

Cobalt (Co) 50.9 ppm

Chromium (Cr) 288 ppm

Copper (Cu) 79.6 ppm

Nickel (Ni) 194 ppm

Zinc (Zn) 117 ppm

Assay Tag 473558 (High Quartz content with small pyrite)

Gold (Au) 2 ppb

Aluminum (Al) 4.64 %

Calcium (Ca) 1.77 %

Iron (Fe) 7.29 %

Magnesium (Mg) 4.91 %

Manganese (Mn) 1170 ppm

Phosphorus (P) 292 ppm

Cobalt (Co) 47.7 ppm

Chromium (Cr) 283 ppm

Copper (Cu) 28.8 ppm

Nickel (Ni) 145 ppm

Zinc (Zn) 95.4 ppm

6226435

01:05:12 p.m.

01-08-2018

Pit/Trench 671/17

Located on Claim 1173909 this area is located close to the southern claim line. It is only 50 meters west of trench 655/17 and could be considered an extension.

The trench is part of a low path that cuts around and between two slopes. We began to clear one side and then continued up the other side.

The overall trench is 16 meters long and 5 meters wide at either end. It contains several ridges as if runs down from both ends. Two samples were taken at this time. The rock contains quartz veins with pyrite.

This is another area where we would follow-up with cross trenches.

Assay Tag 473551 (Fine grain rock host with spider veins of Quartz with pyrite)

Gold (Au) 3 ppb

Aluminum (Al) 2.86 %

Calcium (Ca) 4.34 %

Iron (Fe) 6.00 %

Magnesium (Mg) 1.84 %

Manganese (Mn) 1760 ppm

Phosphorus (P) 529 ppm

Cobalt (Co) 29.2 ppm

Chromium (Cr) 68.3 ppm

Copper (Cu) 92.8 ppm

Nickel (Ni) 36.8 ppm

Zinc (Zn) 85.0 ppm

Assay Tag 473552 (Fine grain rock host with spider veins of Quartz with pyrite)

Gold (Au) 2 ppb

Aluminum (Al) 3.03 %

Calcium (Ca) 1.06 %

Iron (Fe) 6.25 %

Magnesium (Mg) 2.69 %

Manganese (Mn) 964 ppm

Phosphorus (P) 377 ppm

P019

19/34

volunteer thunderbay

01:05:28 p.m. 01-08-2018

Cobalt (Co) 35.3 ppm Chromium (Cr) 35.5 ppm Copper (Cu) 95.7 ppm Nickel (Ni) 38.5 ppm Zinc (Zn) 82.8 ppm

A.M.

volunteer thunderbay

People and Days Worked

Sept 2017

DAA

01-08-2018

Physical: Supervising, traversing, cleaning, sampling.

Terry Yahn

Sept 21, 22, 23, 24

2.58446

6226435

01:05:36 p.m.

volunteer thunderbay

People and Days Worked

Sept 2017

Physical: Supervising, traversing, cleaning, sampling.

Terry Yahn

4 Sept 21, 22, 23, 24

SUMMARY AND CONCLUSIONS

We have already gone a long way in determining the potential for gold in the Shabaqua area. Zone formations from this claim (TB1173909) have developed a pattern which we will continue to expose and sample on all claims we hold in the area. Previous samples ranged from 22 g/t to 54 g/t.

Some of the work we did this time was to re-visit some ground that was not well documented or assayed enough to establish a pattern of where the good gold assays ran.

Other areas that we looked at will give us insight into how we proceed in evaluating this and nearby claims.

We will continue to track and sample in this area as we believe that we have an excellent gold property and that it is worthy of the additional effort.

ATTACHMENTS

SCHEDULE	Theorem 1/425401191 from AGA1 Laboratories \$359.00
SCHEDULE 2	Invoice 921757 from Scott Timmins - John Deere backhoe
SCHEDULE 3	Drawing of Pit/Trench #655/17
SCHEDULE 4	Drawing of Pit/Trench #658/17
SCHEDULE 5	Drawing of Pit/Trench #659/17
SCHEDULE 6	Drawing of Pit/Trench #660/17
SCHEDULE 7	Drawing of Pit/Trench #671/17
SCHEDULE 8	Certificate of Analysis for Gold (Au)
SCHEDULE 9	Certificates A & B – Metals Package, ICP-OES finish
SCHEDULE 10	Map showing contiguous claims for Gold Cache
SCHEDULE 11	Garmin Map Source showing location of Pits/Trenches on Claim

SYMBOLS

SAMPLE SLOPE RIDGE

WATER

ELEVATION

±M

CLAIM #TB 1173909

TRUE

0

UTM LOCATION 164 E0287983 N5385035 NAD 83

PIT/TRENCH #655/17

TO POST #1 METERS BEARING 190

SCHEDULE #3

TOM +om 473553 X 4m +1m

SCALE 2 CM = | M


CLAIM #TB 1173909

SCHEDULE #4

LOCATION 164 FO288100 N5385409 NAD83

PIT/TREVEH #658/17

POST # METERS 756 BEARING 210



SYMBOLS SAMPLE S SLOPE JU RIDGE WATER OUTCROP

ELEVATION IM

SYMBOLS

SAMPLE

SLOPE RIDGE

WATER

BUEVATION ±M


SCHEDULE # 5

CLAIM #TB 1173909

UTM LOCATION 164 E0288192 N5385035 NAD 83

PIT LTRENCH #659/17

POST #1 METERS 608 BEARING



SCALE 3cm=

8 2018 01:21pm

000


CLAIM #TB 1173909

164 E0287865 N5385427 NAD83 LOCATION

PIT / TRENCH #660/17

SCHEDULE #6

POST # METERS BEARING




CLAIM #TB 1173909

UTM LUCATION 160 E0287932 N 5385041 NAD 83

PIT/TREVEH # 671/17

TO POST #1 METERS 1,1 KM BEARING 20°

SCHEDULE #7



SYMBOLS

SAMPLE SY

SLUPE 39

RIDGE IIII

WATTEL SILL

OUTCROP CO

EMEVATION IM

01:07:56 p.m. 01-08-2018





Certificate of Analysis AGAT WORK ORDER: 17B275192

PROJECT:

CLIENT NAME: MISC AGAT CLIENT ON			ATTENTION TO: Terry Yahn							
		(202-052) Fire	Assay - Trace A	u, ICP-OES finish (p	pb)					
DATE SAMPLED: Oct 23, 2017		DATE RECEIVED:	Oct 20, 2017	DATE REPORTED:	SAMPLE TYPE: Rock					
Analyte:	Au									
Unit:	ppb									
RDL:	1									
	3									
	2									
	13									
	1									
	18									
	4									
	3									
	2									
	23, 2017 Analyte: Unit: RDL:	23, 2017 Analyte: Au Unit: ppb RDL: 1 3 2 13	(202-052) Fire 23, 2017 DATE RECEIVED: Analyte: Au Unit: ppb RDL: 1 3 2 13 1 16 4 3 2	(202-052) Fire Assay - Trace A 23, 2017 DATE RECEIVED: Oct 29, 2017 Analyte: Au Unit: ppb RDL: 1 3 2 13 1 10 4 3 2	(202-052) Fire Assay - Trace Au, ICP-OES finish (p 23, 2017 DATE RECEIVED: Oct 20, 2017 DATE REPORTED: Analyte: Au Unit: ppb RDL: 1 3 2 13 1 16 4 3 2	(202-052) Fire Assay - Trace Au, ICP-OES finish (ppb) 23, 2017 DATE RECEIVED: Oct 20, 2017 DATE REPORTED: Nov 03, 2017 Analyte: Au Unit: ppb RDL: 1 3 2 13 1 16 4 3 2	CAGAT CLIENT ON ATTENTION TO: Terry Yahn			

Certified By:

01-08-2018 SCHEDULE 9 A



Certificate of Analysis AGAT WORK ORDER: 178275192

PROJECT:

~=======	. et siere	10100	HON!	CHEN	Cole

AT	TENT	ION	TO:	Tarry	Yahn

						· · · · · · · · · · · · · · · · · · ·					Terry Yah	n			
			(201	-073) Aq	ua Regia	Digest	- Metals	Package	, ICP-OE	S finish	1				
DATE SAMPLED: Oct		DATE RECEIVED: Oct 20, 2017				DATE REPORTED: Nov 03, 2017			SAMPLE TYPE: Rock						
	Analyte:	Ag	A	As	В	Ba	Be	BI	Ca	Cd	Ce	Co	Cr	Cu	· Fe
	Unit:	bbu	%	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm	ppm	ppm	,
Sample ID (AGAT ID)	RDL:	0.2	0.01	1	5	1	0.5	1	0.01	0.5	1	0.5	0.5	0.5	0.01
473551 (8844288)		<0.2	2.86	<1	<5	10	1.5	17	4.34	0.9	13	29.2	68.3	92.8	6.00
473552 (8844289)		0.2	3.03	<1	<5	25	1.2	12	1.06	0.9	9	35.3	35.5	95.7	6.25
473553 (8844290)		0.5	4.88	39	<5	4	0.6	11	9.01	1.1	7	37.3	86.1	109	13.5
473554 (8844291)		0.2	4.18	35	<5	36	<0.5	7	6.55	<0.5	7	38.7	192	83.0	7.37
473555 (8844292)		0.2	0.85	79	<5	52	<0.5	5	2.38	<0.5	20	17.9	10.9	47.2	2.99
473556 (8844293)		0.4	5,39	30	<5	35	1.1	5	1.31	<0.5	5	53.8	347	76.6	7.5
473557 (8844294)		0.3	4.92	39	<5	20	0.9	5	2.77	<0.5	4	50.9	288	79.6	7.15
473558 (8844295)		0.3	4.54	27	<5	17	0.9	5	1.77	<0.5	5	47.7	283	28.8	7.29
												44.1	504	20.0	1.20
	Analyte:	Ga	Hg	ln	ĸ	La	Li ·	Mg	Mn	Ma	Na	NI	P	Pb	Rt
	Unit:	bbu	ppm	ppm	%	ppm	ppm	%	ppm	ppm	%	ppm	ppm	ppm	ррот
Sample ID (AGAT ID)	RDL:	5	1	1	0.01	1	1	0.01	1	0.5	0.01	0.5	10	0.5	10
473551 (8844288)		19	<1	<1	0.01	5	13	1.84	1760	0.6	0.05	36.8	529	3.8	<10
473552 (8844289)		17	<1	<1	0.03	3	20	2.69	964	<0.5	0.04	38.5	377	2.4	
473553 (8844290)		21	2	<1	<0.01	5	10	2.75	3320	<0.5	<0.01	44.2	308	18.4	<10
473554 (8844291)		15	<1	<1	0.16	4	68	3.59	1280	<0.5	<0.01	62.7	443	11.7	<10
473555 (8844292)		6	<1	<1	0.25	8	6	0.79	687	1.3	0.06	48.3	518	7.0	<10
473556 (8844293)		17	<1	<1	0.05	3	48	6.01	1290	<0.5	0.04	233	331	3.3	<10
473557 (8844294)		20	. 1	<1	0.08	4	45	5.31	1280	<0.5	0.02	194	314	6.6	<10
473558 (8844295)		19	<1	<1	0.09	3	46	4.91	1170	1.1	0.02	145	292	3.2	<10
											0.02	1-2	442	3.4	<10
	Analyte:	s	5b	Sc	Se	8n	Sr	Ta	Te	Th	Ti	TI	U	v	w
_ :	Unit:	%	ppm	ppm	ppm	ppm	ppm	ppm	ppm	ppm	%	ppm	ppm	ppm	pper
Sample ID (AGAT ID)	RDL:	0.01	1	0.5	10	5	0.5	10	10	5	0.01	5	5	0.5	1
473551 (8844288)		0.06	<1	14.8	12	16	42.6	16	<10	<5	0.38	<5	A	192	<1
473552 (8844289)		0.04	<1	5.4	11	14	24.3	17	<10	<5	0.32	<5	6	144	
473553 (8844290)		0.78	4	25.2	14	<5	70.4	43	12	<5	0.02	45	18	179	<1
473554 (8844291)		0.23	5	16.9	17	<5	45.7	21	<10	<5	0.02	45	5	181	4
473555 (8844292)		0.51	1	6.0	<10	<5	70.2	<10	<10	<5	<0.01	45	<5	13.0	<1
47355B (8844293)		0.02	1	12.5	15	12	31.4	23	<10	45	0.28	45	9	158	<1
473557 (8844294)		0.04	<1	18.8	12	8	20.4	19	<10	45	0.20	<5	8		<1
473558 (8844295)		0.02	<1	22.8	12	a	23.3	22	<10	45	4.20	< 3	8	159	<1

Certified By:

AGAT CERTIFICATE OF ANALYSIS (VI)

SCHEDYLE 9B




Certificate of Analysis AGAT WORK ORDER: 178275192

PROJECT:

CLIENT NAME: MIS	C AGA I CLIE	NI UN				ATTENTION TO: Terry Yahn						
			(201-	-073) Aqua	Regia Digest - Me	tals Package, ICP-OES finish						
DATE SAMPLED: Oct 23, 2017		DATE RECEIVED: Oct 20, 2017		ED: Oct 20, 2017	DATE REPORTED: Nov 03, 2017	SAMPLE TYPE: Rock						
	Analyte:	Y	Zn	Zr			TOTAL CONTRACTOR OF THE PARTY O					
	Unit:	ppm	ppm	ppm								
Sample ID (AGAT ID)	RDL:	1	0.5	5								
73551 (8844288)		20	85.0	16		**						
73552 (8844289)		15	82.8	17								
173553 (8844290)		12	135	<5								
(73554 (8844291)		10	38.1	<5								
73555 (8844292)		6	15.6	16								
73558 (8844293)		10	100	7								
173557 (8844294)		11	117	<5								
(73558 (8844295)		10	95.4	5								

Certified By:



01:09:01 p.m.

Rece i ved: 6226435

Jan 8 2018 01:23pm

P034

01-08-2018 SCHEPULE

34/3